

2 A9.2 **FLOOR TRANSITION**
SCALE: FULL



3 A9.2 **FLOOR TRANSITION**
SCALE: FULL

FINISH GENERAL NOTES

1. PROVIDE GLASS MAT FACED WATER RESISTANT GYP BD @ ALL CEILINGS IN RESTROOMS, APPROVED ALTERNATE TO CEMENTUOUS BOARD
2. PROVIDE A MINIMUM OF TWO COATS OF PAINT OVER A PRIMER COAT ON ALL DRYWALL
3. STRIP,SEAL AND INSTALL TWO (2) COATS OF JOHNSON WAX ON THE VCT FLOOR PRIOR TO TURNOVER.
4. ALL INTERIOR SURFACES OF H.M. DOOR FRAMES TO BE PAINTED AS NOTED
5. CHAIR RAIL SHALL BE PLACED AT ALL WALLS IN OFFICES AND, BREAK ROOM. DO NOT INSTALL CHAIR RAIL WHERE MILLWORK IS INSTALLED, SEE FLOOR PLAN FOR LOCATION OF MILLWORK PAINT P-1.
6. CEILING INSTALLER IS RESPONSIBLE FOR PROVIDING ADEQUATE WIRE SUPPORTS FOR CHANNELS AT EACH CORNER OF LIGHT FIXTURE
7. APPLY PLYWOOD WAINSCOT TO RECEIVING AREAS, SEALED CLEAR. PLYWOOD TO BE FIRE RETARDANT TREATED
8. WHERE UNDERLAYMENT IS REQUIRED PRIOR TO TILE INSTALLATION, SUB-CONTRACTOR TO PROVIDE "ARDEX K-15 SELF-LEVELING UNDERLAYMENT CONCRETE" AS MANUFACTURED BY ARDEX INC. 630 STOOPS FERRY ROAD CORAOPOLIS, PA 15108 TEL # 412 264-4240
9. SUSPENDED CEILING GRID SYSTEM IS TO BE A STANDARD 15/16" GRID SYSTEM

ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR: SC1 SEALED CONCRETE	FLOOR: PT1 PORCELAIN TILE	FLOOR: PT2 PORCELAIN TILE	FLOOR: PT6 PORCELAIN TILE	FLOOR: PT7 PORCELAIN TILE	BASE: B1 WOOD	BASE: B2 FRP BASE	BASE: B3 RUBBER BASE	BASE: B4 PORCELAIN TILE	WALLS: P1 PAINT	WALLS: P3 PAINT	WALLS: P4 PAINT	WALLS: S1 STAIN	WALLS: PT2 PORCELAIN TILE	WALLS: PT3 PORCELAIN TILE	WALLS: PT4 PORCELAIN TILE	WALLS: PT5 PORCELAIN TILE	WALLS: FRP1 FIBERGLASS PANELS	WALLS: WOOD PANEL	WALLS: WOOD PANEL	WALLS: WOOD CHAIR RAIL (4") CR-1	CEILING: C1 ACOUSTICAL TILE	CEILING: C2 GYPSUM BOARD PAINT P2	CEILING: C3 EXPOSED TO STRUCTURE ABOVE	CEILING HEIGHT	REMARKS	ROOM NO.
101	ENTRY LOBBY		●	●			●				●			●						●			●	●		–	–	101
102	JEWELRY COUNTER		●	●							●	●											●	●		–	–	102
103	JEWELRY COUNTER		●	●							●												●	●		–	–	103
104	JEWELRY SALES		●				●				●	●											●			–	–	104
105	STORAGE		●						●		●															–	–	105
106	SERVER CLOSET		●						●		●												●			–	–	106
107	OFFICE		●				●				●												●			–	–	107
108	TOILET ROOM		●		●	●										●	●				●			●		–	–	108
109	CASHIER		●				●				●												●			–	–	109
110	VAULT	●								●	●													●		–	–	110
111	JEWELERS				●					●									●				●			–	–	111
112	COAT CLOSET		●							●	●												●			–	–	112
113	TOILET ROOM		●												●	●			●				●			–	–	113
114	LOAN COUNTER		●								●												●			–	–	114
115	GUN VAULT									●	●													●		–	–	115
116	STORAGE									●	●													●		–	–	116
117	EXIT VESTIBULE		●				●				●												●			–	–	117
118	STORE ROOM									●													●			–	–	118
119	MECHANICAL ROOM	●								●	●								●				●			–	–	119
120	BREAK ROOM		●	●			●				●			●			●				●		●			–	CHAIR RAIL CR-1 AT 32" A.F.F. S-1	120
121	TOILET ROOM		●		●	●										●	●				●			●		–	–	121
122	TOILET ROOM		●		●	●	●									●	●				●			●		–	–	122
123	JANITOR	●																								–	–	123
124	STORE ROOM																									–	–	124

INTERIOR FINISH LEGEND

DESIGNATION	DESCRIPTION	STYLE	COLOR	MANUFACTURER	CONTACT:	REMARKS:
FLOOR FINISHES						
PT1	PORCELAIN TILE	STRATOS-APOLO	BEIGE/POLISHED-- 16" x 31 3/4"	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR FLOOR PATTERN
PT2	PORCELAIN TILE	STRATOS-ORION	MARRON/POLISHED-- 12" X 24"	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR FLOOR PATTERN
PT6	PORCELAIN TILE	STRATOS-ORION	MARRON/POLISHED-- 4" X 24"	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR FLOOR PATTERN
PT7	PORCELAIN TILE	AVILA MOSAIC	ARENA/MATT-- 1" X 2"	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR FLOOR PATTERN
R1	RUBBER FLOORING	----	----	----	----	----
SC1	SEALED CONCRETE	----	----	----	----	----
BASE FINISHES						
B1	BIRCH WOOD	4" WOOD BASE	STAIN	----	----	----
B2	FRP BASE MOLDING	M612	ALMOND	MARLITE	----	----
B3	RUBBER BASE	----	100 BLACK	ROPPE	----	----
B4	PORCELAIN TILE	----	----	----	----	----
WALL FINISHES						
P1	PAINT		INDIAN LEGEND -A0083	ICI PAINTS	DALE READY 832-427-9267	----
P3	PAINT		HIGHLAND PLAINS -A1768	ICI PAINTS	DALE READY 832-427-9267	----
P4	PAINT		TUSCAN TAN -A0083	ICI PAINTS	DALE READY 832-427-9267	----
S1	STAIN		BISTRO WALNUT -SW3115 B	SHERWIN WILLIAMS	BRIAN G PATTON 713-957-4209	----
PT3	PORCELAIN TILE	STRATOS ORION	BLANCO POLISHED- 12" X 24"	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR PATTERN
PT4	PORCELAIN TILE	VAIL	IVORY BORDER MOSAIC	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR PATTERN
PT5	PORCELAIN TILE	VAIL	SAHARA BORDER MOSAIC	ROCA TILE GROUP	ALEJANDRO GARCIA 713-409-3622	RE: DWG FOR PATTERN
WD2	BIRCH WOOD	WAINSCOATING	STAIN	----	----	----
FRP1	FIBERGLASS PANEL	STANDARD	ALMOND	MARLITE		
CEILING FINISHES						
P2	PAINT		PACIFIC MIST -A0064	ICI PAINTS	DALE READY 832-427-9267	----
C1	ACCOUSTICAL PANEL	CIRRUS ANGLED TEGULAR	WHITE	ARMSTRONG	----	----
C2	GYPSUM BOARD	----	----	----	----	PAINTED P2
C3	EXPOSED CEILING	----	----	----	----	----
LAMINATES						
PL1	PLASTIC LAMINATE		HAMPTON WALNUT 7959K-78	WILSONART	BRAD PUSER 713-957-4209	----
PL2	PLASTIC LAMINATE		DESIGNER WHITE D354	WILSONART	----	----
MISCELLANEOUS						
MTL1	METAL TRIM	JOLLY	ATG-BRUSHED NICK ANO 3/8"	SCHLUETER	SCHLUETER 800-472-4588	RE: ELEVATION FOR LOCATION
MTL2	METAL TRIM	REVEAL PANEL TRIM	VERTICAL TRIM 1"-NICK ANO	FRY REGLET	FRY REGLET 800-237-9773	----
WD3	BIRCH WOOD	5/8" X 2" WOOD BAND	STAIN	----		----
ST1	STONE COUNTERTOPS	GRANITE	CREAM GOLD	----		1/2" WITH A 1 1/2" EASE EDGE
CERAMIC TILE GROUT						
GRT1	GROUT	SPECTRA LOCK	81-BUTTER CREAM	LATICRETE		
GRT2	GROUT	SPECTRA LOCK	41-KASHMIR	LATICRETE		

Hermes Architects
Members A.I.A.
1177 West Loop South, Ste. 500
Houston, Texas 77027
Tel. 713-785-3644
www.hermesarchitects.com
Houston · Dallas/ Ft. Worth

This document is an instrument of service protected by the copyright law of the United States of America, 17 U.S.C. § 102, and shall not be copied or reproduced without the express written consent of Hermes Architects, Inc.

Shaw's Jewelers
West Gray
1021 West Gray Ave.
Houston, Texas

Shaw's Jewelers
1014 West Gray Street
Houston, Texas 77019

DATE	11.11.2011
PROJECT NO.	1102100
DRAWN BY	--
CHECKED BY	

Finish Schedule

A9.2

____ OF ____

COPYRIGHT © 2011 Hermes Architects, Inc.

K:\1102100\DRAWINGS\4-PLOT SHEETS\SHEETS\A9.2 FINISH SCHEDULE.DWG 11/9/2011 8:17:53 AM DARREN PENEWITT